



कुमाऊँ विश्वविद्यालय, नैनीताल(उत्तराखण्ड)
KUMAUN UNIVERSITY, NAINITAL (UTTARAKHAND)

पत्रांक-केयू/उत्तराखण्ड/2021-22/205

दिनांक 22-09-2021

निविदा तिथि विस्तारीकरण सूचना

विश्वविद्यालय के पत्रांक केयू/तकनीकी/2021/विनियो/346 दिनांक 03-09-2021 द्वारा आमंत्रित निविदा जो पूर्व में दिनांक 20-09-2021 को खोली जानी थी उक्त तिथि को विस्तारित कर दिनांक 28-09-2021 तक किया जाता है। निविदा फार्म को विश्वविद्यालय की वैबसाइट www.kunainital.ac.in से दिनांक 27-09-2021 तक डाउनलोड किया जा सकता है अन्य शर्तें पूर्ववत रहेंगी।

(दिनेश चन्द्रा)
कुलसचिव

प्रतिलिपि- निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

- 1- श्री केके पाण्डे, कम्प्यूटर प्रोग्रामर को इस आशय से प्रेषित कि उक्त सूचना को विश्वविद्यालय की वैबसाइट में अपलोड करे।
- 2- विश्वविद्यालय के पंजीकृत ठेकेदारों को ई-मेल से सूचनार्थ
- 3- प्रशासनिक भवन सूचना पट्ट

(दिनेश चन्द्रा)
कुलसचिव



निविदा प्रपत्र

- 1-प्रत्येक कार्य हेतु पृथक-पृथक निविदा फार्म सीलबन्द लिफाफे में अधोहस्ताक्षरी के कार्यालय में निर्धारित तिथि एवं समय तक डॉक/निविदा बॉक्स में डाली जानी आवश्यक होगी।
- 2- प्रत्येक निविदा के साथ रू0 100 का नॉन ज्यूडिशियल स्टाम्प पर एक रूपये का हस्ताक्षरयुक्त रसीदी टिकट प्रेषित करना अनिवार्य होगा।
- 3-प्रत्येक निविदा के साथ निर्धारित धरोहर राशि एफ0डी0आर0/एन0एस0सी0 के रूप में वित्त अधिकारी, कुमाऊँ विश्वविद्यालय, नैनीताल के पक्ष में बन्धक बनाकर संलग्न करनी आवश्यक होगी।
- 4-निविदा फार्म निर्धारित शुल्क में लेखा अनुभाग से या वित्त अधिकारी के पदनाम से डिमांड ड्राफ्ट बनाकर प्राप्त किये जा सकते हैं।
- 5- निविदादाता को चाहिए कि वे निविदा देने से पूर्व कार्यस्थल का निरीक्षण कर लें।
- 6-समस्त कार्य लोक निर्माण विभाग द्वारा समय-समय पर निर्गत निर्धारित मानकों/शर्तों के अनुरूप सम्पादित किये जायेंगे।
- 7-किसी एक/समस्त निविदा को स्वीकृत/अस्वीकृत करने का अधिकार अधोहस्ताक्षरी के पास सुरक्षित होगा।

कुलसचिव

(10/5)

Tender form

Name of work- Repair and maintenance work of old building at K.U. NTL allotted to shri Kailash Bisht.

Date of calling Tender- 03-09-2021

Date of Opening Tender-20-09-2021

Cost of Tender form- Rs. 1180.00

Earnest Money Rs. 11000.00

Time of completion- 45 Days

Validity of Tender- 45 Days

S.N.	PARTICULARS ITEM	QUANTITY	UNIT	ESTIMATE D RATE IN (Rs.)
1	20mm cement plaster of mix:13.3.2 :1:6(1 cement:6fine sand	155.62	sqm	414.75
2	15mm cement plaster on rough side single or half brick wall of mix: 13.5.2:1:6(1cement:6 coarse sand)	70.56	sqm	369.45
3	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade:13.41.1	376.18		184.10
4	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in charge.	226.18	sqm	62.00
5	Painting with synthtic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	34.56	sqm	212.58
6	Dismantling roofing including ridges, hips valleys and gutters etc. GS sheet.	14.07	sqm	146.25
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering –All work up to plinth level 1:2:4 cement c sand and 20mm stone aggregate.	6.05	cum	8146.3
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair casses above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement wityh 1:1,5:3(1 cement : 1.5 coarse sand (Zone-III) :3 graded stone aggregate 20 mm nominal size)	0.78	cum	11716.55
9	Centering and shuttering including strutting, proping etc, and removal of form for suspended floors, roofs, landings, balconies and access platform/Shelves (Cast in situ)	9.72	sqm	831.65
10	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and medium tensile steel bars	91.84	Kg	98.50
11	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked stainless steel butt hinges with necessary screws.	11.02	sqm	2183.75
12	Steel work in built up tubular hollow tubes etc. including cutting, hoisting , fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	464.80	Kg	172.10
13	Steel work welded in buit up sections/framed work, including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc, as required. in grating, frames , guard bar, ladeer, railing, brackets, gates and similar works.	85.00	Kg	157.20
14	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1 st quality conforming to IS: 15622 of approved make in colours such as white, Ivory, grey, fume red brown, laid on 20 mm thick cement mortar 1:4(1 Cement:4 Coarse sand), Jointing with grey cedment slurry @3.3 Kg/sqm including pointing the joints with white cemednt and matching pigment etc. complete.	29.72	sqm	1112.25

15	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limper washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal /vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zine coating not less than 275 gm/m ²	24.75	sqm	1098.00
16	Providing ridges or hips of width 60cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zine coating not less than 275 gm/m ²	5.00	rm	852.15
17	Providing and fixing flat pressed 3 layer particle board medium density exterior grade (Grade I) or graded wood particle board IS: 3087 marked, to frame, backing or studding with screws etc. complete (frames, backing or studding to be paid separately): 18 mm thick.	14.07	sqm	1098.70
18	Providing fixing GI metal Ceiling lay in plain tegular edge global white color tiles of size 595x595 mm, and 0.5 mm thick with 8mm drop, made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	46.83	sqm	1805.30

Note- All the work shall be carried out as per P.W.D. specification and directed by engineer I/C

I/We tender.....% below/above on the given Estimated Rates

Sig. of Contractor
(with full address)


Registrar